



Layout Material List Report

CUSTOMER Lawrence Residence
 PROJECT NAME
 ADDRESS
 ADDRESS 2
 BROKEN-DO NOT

Job: SR-263361

Level: 2nd Floor

Framing Connector Summary

PlotID	Qty	Manuf	Product	Bk Blks	Web Stiff
H1	2	Simpson	HHUS410	No	No
H2	54	Simpson	IUS2.06/11.88	No	No
H3	9	Simpson	IUS3.56/11.88	No	No
H4	1	Simpson	MIU4.28/11	No	No
H5	1	Simpson	MIU4.28/11	No	Yes

Products

Plot ID	Length	Product	Plies	Net Qty
F16'-2	16'0"0	11 7/8" TJI® 210	2	2
F16'	16'0"0	11 7/8" TJI® 210	1	4
F12'	12'0"0	11 7/8" TJI® 210	1	10
F10'-2	10'0"0	11 7/8" TJI® 210	2	4
F10'	10'0"0	11 7/8" TJI® 210	1	38
F8'-2	8'0"0	11 7/8" TJI® 210	2	2
F8'	8'0"0	11 7/8" TJI® 210	1	3
F4'	4'0"0	11 7/8" TJI® 210	1	3
FBk1	1'3"8	11 7/8" TJI® 210	1	1
X20'	20'0"0	11 7/8" TJI® 560	1	11
M1-3	20'0"0	1 3/4" x 11 7/8" 2.0E Microllam® LVL	3	3
M2-2	16'0"0	1 3/4" x 11 7/8" 2.0E Microllam® LVL	2	2
M4-3	14'0"0	1 3/4" x 11 7/8" 2.0E Microllam® LVL	3	9
M3-2	14'0"0	1 3/4" x 11 7/8" 2.0E Microllam® LVL	2	2
PPT1	10'0"0	3 1/2" x 5 1/4" 1.8E Parallam® PSL	1	5
STCa1	16'0"0	1 1/8" x 11 7/8" TJ® Rim Board	1	11

Wall Framing

Plot ID	Length	Product	Plies	Net Qty
MHd1-2	8'0"0	1 3/4" x 11 7/8" 2.0E Microllam® LVL	2	2
MHd2-2	6'0"0	1 3/4" x 9 1/4" 2.0E Microllam® LVL	2	2

Accessories

Plot ID	Length	Product	Plies	Net Qty
	9"2	3/4" x 2 5/16" Web Stiffeners	1	2
	0	23/32"x48"x96" Weyerhaeuser Edge Gold Panel (0/24) T&G SF	1	47

Total Lengths

Length	Product
689'3"8	11 7/8" TJI® 210
220'0"0	11 7/8" TJI® 560
262'0"0	1 3/4" x 11 7/8" 2.0E Microllam® LVL
12'0"0	1 3/4" x 9 1/4" 2.0E Microllam® LVL

(†) User modified item. (‡) User added item.

Layout Material List Report

Job: SR-263361

50'0"0	3 1/2" x 5 1/4" 1.8E Parallam® PSL
176'0"0	1 1/8" x 11 7/8" TJ® Rim Board
1'6"4	3/4" x 2 5/16" Web Stiffeners

Layout Material List Report

Job: SR-263361

Level: Roof

Products

Plot ID	Length	Product	Plies	Net Qty
M1-2	12'0"0	1 3/4" x 9 1/4" 2.0E Microllam® LVL	2	2

Total Lengths

Length	Product
24'0"0	1 3/4" x 9 1/4" 2.0E Microllam® LVL